Solar System Installation Guide

Pre-Installation

Site Assessment

1. Roof Evaluation

- Age and condition of roof
- Structural integrity
- Shading analysis
- Available mounting space

2. Electrical Assessment

- Main service panel capacity
- Grounding system
- Interconnection point
- Backup power requirements

3. Documentation

- Building permits
- Utility interconnection agreement
- HOA approval (if required)
- Engineering calculations

Safety Requirements

Personal Protection Equipment

- Hard hat
- Safety glasses
- Steel-toed boots
- Fall protection harness
- Work gloves
- High-visibility vest

Job Site Safety

- OSHA compliance
- Fall protection setup
- Fire safety equipment
- First aid kit
- Emergency contact information
- Safety perimeter establishment

Installation Process

1. Roof Preparation

- Clean work area
- Locate and mark rafters

- Install mounting points
 - Flash all roof penetrations
 - Ensure proper sealing
 - Maintain proper spacing

2. Racking Installation

- Install rails according to design
- Level and align all components
- Torque to specifications
- Weather sealing
- Grounding/bonding

3. Panel Installation

1. Panel Preparation

- Inspect all panels
- Install optimizers (if used)
- Attach mounting hardware

2. Mounting Process

- Secure panels to rails
- Maintain proper spacing
- Install end clamps
- Torque all connections

4. Electrical Installation

DC Wiring

1. String Configuration

- Follow wiring diagram
- Maintain proper polarity
- Use appropriate wire gauge
- Install disconnects

2. Wire Management

- Secure all cables
- UV protection
- Proper bend radius
- Label all conductors

AC Wiring

1. Inverter Installation

- Mount securely
- Maintain clearances
- Connect AC and DC
- Install rapid shutdown

2. Grid Connection

- Install AC disconnect
- Connect to main panel
- Install production meter
- Label all components

5. Monitoring Setup

- Install gateway
- Configure network
- Test communication
- Verify data reporting

Quality Control

System Verification

1. Mechanical Inspection

- All mountings secure
- Proper torque on bolts
- Roof integrity verified
- No panel damage

2. Electrical Testing

- Continuity checks
- Voltage measurements
- Polarity verification
- Insulation resistance
- Ground fault check

Documentation

- As-built drawings
- String map
- Photos of installation
- Test results
- Permit signatures

System Commissioning

Startup Procedure

1. Pre-Power Checklist

- · All connections verified
- All switches off
- Area clear of personnel

2. Power-Up Sequence

- DC activation
- AC activation
- Inverter startup
- System monitoring

Performance Verification

- Production test
- Efficiency check
- Communication test
- Safety system check

Customer Handoff

Documentation Package

- Warranty information
- Operation manual
- Maintenance schedule
- Emergency procedures
- Contact information

Customer Training

- Basic operation
- Monitoring system use
- Safety procedures
- Maintenance requirements
- Troubleshooting guide

Maintenance Access

Service Points

- Inverter locations
- Disconnect positions
- Monitoring equipment
- Junction boxes
- Ground points

Access Requirements

- Roof access points
- Equipment clearances
- Safety tie-off points
- Storage of spares

Emergency Procedures

Shutdown Sequence

1. Normal Shutdown

- AC disconnect
- DC disconnect
- Verification

2. Emergency Shutdown

- Rapid shutdown activation
- Main disconnect
- Emergency services info

Emergency Contacts

• System installer

- Utility company
- Fire department
- Technical support
- Monitoring service

Appendix

Tools Required

- Torque wrench
- Multimeter
- Wire strippers
- Conduit bender
- Level
- Power drill
- Socket set

Fastener Specifications

- Mounting bolts
- Rail clamps
- Panel clamps
- Ground lugs
- Wire management

Reference Documents

- NEC requirements
- Local codes
- Manufacturer specs
- Warranty terms
- Utility requirements